

**SURVEY &  
REMONUMENTATION**

1 MAY 28 1997

2 COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

Richland

1. Public Land Survey

T 1 S R 10 W

F-09

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_


5. Private Claims \_\_\_\_\_

Clerk-Register  
*Jessica M. [Signature]*

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
96 AUG 26 PM 4 01

Register of Deeds Stamp & File Number

LIBER 2 PAGE 052

|    |   |    |   |    |   |   |   |    |   |    |   |    |   |
|----|---|----|---|----|---|---|---|----|---|----|---|----|---|
| 1  | A | B  | C | D  | E | F   | G | H  | I | J  | K | L  | M |
| 2  |   | 6  |   | 5  |   | 4   |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |   |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9   |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |   |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16  |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |   |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21  |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |  |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28  |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |   |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33  |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |   |   |    |   |    |   |    |   |

I, Robert E. Snell, in a field survey on April 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

1826: United States Government surveyors; set  $\frac{1}{4}$  section post.  
Wh. Oak 30" South 14 lks.  
Y. Oak 14" N 2° W 38 lks.

1887: F. Hodgman, County Surveyor; found stake and stone and stump of bearing tree NW all in place. Set post.  
Wh. Oak 8" S 66° W 9½ lks.  
Wh. Oak 8" N 57° E 24 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1956: Wilkins and Wheaton Engr. Co.; found tile in line with North and South fence. Fence to North 1.1'.  
12" Hickory East 12.90'  
12" Hickory N 45° E 5.55'  
12" Hickory S 85° W 18.15'

1996: Found tile at surface of ground.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-18-1996**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-09: South  $\frac{1}{4}$  post Section 21, T 1 S, R 10 W; ratified by the Kalamazoo County Remonumentation Program Peer Group on July 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman, County Surveyor in 1887 remonumentation survey. Placed remonumentation sleeve over tile.  
PK nail on North side 14" Cherry N 85° W 8.50'  
PK nail on West side 16" Hickory N 45° E 5.40'  
PK nail on North side 8" Hickory S 40° W 7.40'  
PK nail on West side 14" Oak North 37.25'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 8-22-1996