



LC-000101  
 Page: 1 of 1  
 12/28/1999 03:51P  
 BK-2 Pg-554

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in RICHLAND TOWNSHIP  
KALAMAZOO Located In: Corner Code #  
 (County)

- |                                    |                                     |             |
|------------------------------------|-------------------------------------|-------------|
| 1. Public Land Survey              | T <u>1S</u> R <u>10W</u>            | <u>F-13</u> |
|                                    | T <u>  </u> R <u>  </u>             | <u>  </u>   |
|                                    | T <u>  </u> R <u>  </u>             | <u>  </u>   |
|                                    | T <u>  </u> R <u>  </u>             | <u>  </u>   |
| 2. Property Controlling in Section | S <u>  </u> T <u>  </u> R <u>  </u> | <u>  </u>   |
|                                    | S <u>  </u> T <u>  </u> R <u>  </u> | <u>  </u>   |
| 3. Miscellaneous Property in Sec.  | S <u>  </u> T <u>  </u> R <u>  </u> | <u>  </u>   |
|                                    | S <u>  </u> T <u>  </u> R <u>  </u> | <u>  </u>   |

**SURVEY & REMONUMENTATION**

**FEB 08 2000**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 6. IWM Job No. 32252

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on November, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP 12-09-1999**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1825 - Mullett (V. 5, P. 166), Set qt. Sec. post, Oak 9" N: 76 1/2° E. 57 lks., Oak 10" N. 84° W. 168 lks.
  - 1887 - Hodgman (V. 2, P. 211), Fd stk S. 84° E. 168 lks (110.9') from W. Oak stump of B.T., set post
  - 1894 - Strong (V. 3, P. 65), Tile at S 1/4 of Sec. 33, the jog is 6 lks more than the 1/2 sum of the Sec corners jogs. Strong measures jog at 106.59 feet to N 1/4 Sec. 4. He set on bisection.
  - 1932 - W&W, Fd tile 1' below surface of road, 12" Hic N. 42° E. 53.55', 16" Hic S. 62° W. 50.0', 4" Oak S. 43° E. 36.98', 6" Hic S. 45° W. 44.5', 6" Oak S. 10° W. 23.45', Iron in line North 27.53'
  - 1972 - Gove (L. 1, P. 243), Fd Iron rod, 12" Hic N. 60° E. 74.45', Fence North 34.03', P.P. S. 60° W. 74.85'
  - 1981 - Ingersoll, Watson & McMachen, Inc., No surface marker found
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No surface marker found. Found empty mon. box 8' South in center line travelway. Dug 4X4X4 at 106' West of bisection, found no evidence. Dug below empty mon. box, found no evidence.

**RE-ESTABLISH SOUTH 1/4 CORNER:** 1894 (V. 3, P. 65), Strong states that for N 1/4 of Sec. 4 Comstock he bisected the North Section line, and that the jog (to tile at S 1/4 Section 33 Richland) is 6 links more than the 1/2 sum of the Section corner jogs, Hic 7" N. 3 1/2° E. 34 lks (22.44), Oak 10" S. 27 1/4° W. 47 1/2 lks (31.3), Rec. jogs at NW 180 lks., at NE 131 = 311/2 = 155.5, Strong shows meas of 161 1/2 (106.59).

Ingersoll, Watson & McMachen, Inc. found tile at NW cor. and brick at NE cor., measured and bisected mile between. Found Strong's Hickory tree witness still standing (now 23"). Held witness tree and bisected distance and reset N 1/4 Sec. 4 at intersection. Projected a line from found tile at SE cor. Sec. 33 through set N 1/4 of Sec. 4, measured 106.59 and reset S 1/4 Sec. 33.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Position as established in Section "B" above is accepted as a careful and faithful reestablishment of the position of the original corner. Placed 30" Harrison Monument at said above position with monument box over, Accessories:

- "PK" nail in East side of wood fence post North 29.58'
- "PK" nail in NW'ly side of 24" Hickory N. 75° E. 71.97'
- "PK" nail in NW'ly side of U. Pole S. 65° W. 77.43'
- Iron rod placed S. 65° E. 71.59'
- 5.8' North of centerline East & West road
- In line with fence extending North

Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 12/28/99

