

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

DEC 15 PM 1 37

For corners in **RICHLAND TWP.**

KALAMAZOO (County) Located In: Corner Code #

1. Public Land Survey	T <u>1</u> S R <u>10</u> W	<u>H-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. [Signature]
 CLERK-REGISTER

LIBER **1** PG **1227**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **Allen H. McMachen** a field survey on May 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1880'S - F. Hodgeman C.S. Place Clay Tile Post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Clay Tile below concrete Plat Monument.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 11-17-94 *R.H.S.*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found Clay Tile is accepted as a careful & faithful perpetuation of the original corner. Removed concrete Plat Monument and replaced with Harrison Monument over existing Tile.
 Accessories:

- Nail & Tab in 14" Oak N. 10° W. 8.01'
- Nail & Tab in 10" Maple EAST 6.00'
- Nail & Tab in Triple Cherry SOUTH 42.33'
- Nail & Tab in 14" Osage Orange WEST 36.29'

Signed by Allen H. McMachen Date 11/30/94
 Surveyor's Michigan License No. 16935