

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Kalamazoo

(County)

Richland  
1. Public Land Survey

Located In:	Corner Code #
T 1S R 10W	H-11
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling in Section  
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
96 AUG 26 PM 4 01  
Jamaal Stamps  
CLERK - REGISTER  
Register of Deeds Stamp & File Number  
LIBER 2 PAGE 050

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11							34						
12	31		32		33				35		36		
13													

I, Robert E. Snell, in a field survey on May 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government surveyors; set 1/4 section post.  
Wh. Oak 18" S 55° W 225 lks.  
Wh. Oak 10" N 4° E 267 lks.

1887: F. Hodgman, County Surveyor; found stake S 4° W 267 lks. from stump of Wh. Oak bearing tree. Set post.  
Y. Oak 12" S 77 1/2° E 47 1/2 lks.  
Double Y. Oak 8" N 21 1/2° E 101 1/2 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No Date: Acro Engineering Co. files show iron over tile.  
1996: Found 5/8" x 18" long iron bar over tile 30" deep.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
7-18-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11: North 1/4 post Section 34, T 1 S, R 10 W; ratified by the Kalamazoo County Remonumentation Program Peer Group on July 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman, County Surveyor in 1887 remonumentation survey. Placed 20" Harrison over tile in monument box.  
PK nail on West side 24" Oak N 50° E 44.53'  
PK nail on East side 22" Walnut S 20° E 63.59'  
PK nail on East side 16" Pin Oak S 42° W 38.64'  
PK nail on East side 8" Triple Maple 8" N 20° W 59.08'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 8-22-96