

OCT 06 1997

COMMISSION

LIBER

2 PAGE 215

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.
Kalamazoo
(County)

Located In:

Corner Code #

| | | | | | |
|--------------------------------------|---|------------|---|-------------|-------------|
| 1. Public Land Survey | T | <u>1S.</u> | R | <u>10W.</u> | <u>I-10</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | R | | |
| | S | | R | | |
| 3. Miscellaneous Property in Section | S | | R | | |
| | S | | R | | |

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 SEP 26 AM 11 10
Annexed
CLERK - REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 30443-97

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Allen H. McMachen, in a field survey on August 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - John Mullett, D.S., Set 1/4 Section post, Y. Oak 16" S. 85° W. 553 lks., Wh. Oak 14" N. 70 1/2° E. 333 lks.
- 1872 - S. Hodgman, D.C.S., "Sec. corner - Stone by S. Pratt, Surveyor 19" West of tree line between Section corners, set side stones S. 45° E. & N. 45° E., each 70 1/4 lks. (46.7').
- 1887 - F. Hodgman, C.S., "Found stone of former survey in place, set post. Maple 4" N. 78° E. 55 lks. (36.30'), Maple 4" S. 43° E. 82 lks. (54.12').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in mon. box, removed iron and dug to depth of 3' finding clay tile. Tile is 0.2' East of surface iron location. Monument box also found 29' North of tile (box empty).

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-18-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over found clay tile with monument box over, Accessories:

- Nail & Tab in N.W. side of 28" Maple N. 30° E. 73.80'
- Nail & Tab in South side of 22" Maple N. 85° E. 36.50'
- Nail & Tab in East side of 42" Maple S. 45° E. 54.40'
- Nail & Tab in South side of 6" Walnut S. 70° W. 78.00'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 9/26/97