

'94 APR 28 AM 9 11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Sec. 2, Richland Twp.

1. Public Land Survey

T 1 S R 10 W

J-3

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
 in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous

S ___ T ___ R ___

Property in Sec.

S ___ T ___ R ___

James J. Jones

CLERK-REGISTER

LIBER

1 PC 1135

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										X			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on March 2, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner set by U.S. Government Survey-Set 1/4 Section Post.

Wh. Oak 16" South 05° East 41 Lks

Wh. Oak 15" North 20° West 63 Lks

1887-F.Hodgeman, County Surveyor-Found stone and brick in hedge, North 05° West, 41 Lks from stump of 30" Bearing Tree. Set Post.

Hickory 10" South 77 1/2° East 15 1/2 Lks

Hickory 12" North 05 1/2° East 167 1/2 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile with "X" on top.

R. E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 South 1/4 Post, Section 2, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found 3" round clay tile with "X" on top as called for in 1887 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

East and West Fence South 0.80'

PK Nail in 40" Hickory South 77° East 10.20'

4" Iron Fence Post East 26.95'

PK Nail in 15" Oak North 20° West 63.00'

Signed by

Robert E. Snell

Date

4-26-94

Surveyor's Michigan License No.

9734