

1
2

STATE OF MICHIGAN
COUNTY OF KALAMAZOO

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
94 MAR 21 AM 11 21

For corners in
Kalamazoo

(County)

Located In:

Corner Code #

- 1. Public Land Survey T .1 S. R .10 W. J-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

James E. Young

CLERK-REGISTER

LIBER

1 PG 1129

Register of Deeds Stamp & File Number

- 4. Lot No. N/A , Recorded Plat N/A
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GREGORY N. JENSEN , in a field survey on 3/10/94 , 19 94 , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
 - a-SET POST 1826 GLO SURVEY, WHITE OAK 30" EAST, 49 LKS. (32.34')
 - YELLOW OAK 30" N.35'W, 159 LKS. (104.94')
 - F. HODGEMAN COUNTY SURVEYOR - FOUND STAKE FROM BEARING TREES STANDING SET POST. (CLAY TILE)
 - WILKINS & WHEATON 11/6/59 - T.H. FOUND CLAY TILE 2.99' SOUTH OF 3' STEEL POST.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - b-FOUND SOLID CLAY TILE W/ CROSS 2.99' SOUTH OF 3" STEEL POST 0.3' BELOW SURFACE.

R.S.S. RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-3-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - c- J-5 SOUTH 1/4 POST OF SECTION 11, T.1 S., R.10 W., RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PROGRAM PEER GROUP ON MARCH 3, 1994. FOUND CLAY TILE CALLED FOR BY F. HODGEMAN COUNTY SURVEYOR AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. PLACED REMONUMENTATION SLEEVE OVER TILE.

CENTERLINE 3" STEEL FENCE POST W/ BRACE, NORTH 3.2'
 CENTERLINE OF POWER POLE, N 85' W - 34.55'
 CENTERLINE OF 10" OAK, N 30' W - 80.9'
 N. & S. CHAIN-LINK-FENCE, EAST - 6.2'; E. & W. STOCKADE FENCE, SOUTH 3.0'



Signed by *Gregory N. Jensen*
 Surveyor's Michigan License No. 3/21/94 - 31593

Date 3/21/94