

FEB 08 1999

LIDER

PAGE 431

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T1S R10W	J-06
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 29 AM 11 26
Clerk - Register
[Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors.

1957: Wilkins & Wheaton Engr. Co.; established center of Section 14, T. 1 S., R. 10 W. by intersection of 1/4 lines.

Corner Face 18"x18" concrete post	Northwest	28.73'
Corner Face 18"x18" concrete post	North	24.2'
Top Face 18"x18" concrete post	South	34.69'
18" W. Cherry	N. 60° W.	54.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Found iron in monument box as set in 1957 on intersection of 1/4 lines dug with backhoe a hole 4'x6'x3½' deep centered on position of monument box. Found no other evidence.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-17-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-06: Center 1/4 post, Section 14, T. 1 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 17, 1998 and is accepted as the best available evidence of the position of the corner. Found ½"x18" iron rerod as placed by Wilkins & Wheaton Engr. Co. in 1957 survey in monument box. Placed 30" Harrison monument in monument box in place of iron.

Northeast Corner at Top	18"x18" Concrete Post	S. 10° W.	34.71'
60d Nail in Southeast Root	28" Wild Cherry	N. 58° W.	54.05'
Nail/Tab in Northwest Side	36" Maple	S. 60° E.	97.50'
"x" in South Rim	Monitoring Well	N. 18° W.	32.30'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 12-29-98