

**SURVEY & REMONUMENTATION**

1  
2 AUG 06 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 002

For corners in Kalamazoo (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Richland Twp.

1. Public Land Survey	T <u>1</u> S. R <u>10</u> W.	<u>K-06</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 '96 MAR 23 PM 1  
 Register of Deeds Stamp & File Number  
 Clerk-Register

I, Robert E. Snell, in a field survey on April 29, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1826: United States Government Surveyors; set 1/4 Section post.  
 W. Oak 18" S. 39° W. 28 lks.  
 Hickory 7" N. 50° E. 37 lks.
- 1887: F. Hodgman, County Surveyor; found old rotten stake in center of road and in line with fence south. Cavity of bearing tree S. 39° W. 28 lks. set post. Y. Oak 18" N. 60° E. 74½ lks., Wh. Oak 16" N. 75° W. 119 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1946: Wilkins & Wheaton Engr. Co.; found tile.  
 34" Oak NW 78.63'  
 24" Oak SE 61.72'  
 10" Ironwood SW 44.35'
- 1996: Found 1/2" x 12" iron bar in monument box over tile with cross in top, 21" deep.

**RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP**  
 5-16-1996

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-06: East 1/4 post Section 14, T. 1 S., R. 10 W., Ratified By the Kalamazoo County Remonumentation Peer Group on May 16, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with cross on top as set by F. Hodgman, County Surveyor in a remonumentation survey in 1887 inside a monument box. Set a 18" Harrison Monument over tile in monument box.

PK Nail in East Side	28" Hickory	South	80.20'
PK Nail in North Side	32" Oak	S. 60° E.	61.87'
PK Nail in North Side	18" Hickory	S. 60° W.	44.24'
PK Nail in North Side	24" Cherry	N. 64° W.	94.28'

Signed by Robert E. Snell Date 5-23-96