

**SURVEY & REMONUMENTATION COMMISSION**

1  
2 AUG 06 1996  
COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 003

For corners in Kalamazoo (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Richland Twp.

1. Public Land Survey	T <u>1</u> S. R <u>10</u> W.	<u>K-07</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
'96 MAY 23 PM 1  
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on April 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1826: United States Government Surveyors; set post common to Sections 13, 14, 23 and 24.  
 Wh. Oak 20" N. 2° E. 640 lks.  
 Burr Oak 16" S. 88° E. 622 lks.
  - 1887: F. Hodgman, County Surveyor; found stake and brick N. 38½° W. 68 lks. from Maple 12" bearing tree of resurvey. Set post.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- 1946: Wilkins & Wheaton Engineering Co.; found tile.  
 Maple 10" S. 38° E. 44.90'  
 Maple 16" S. 55° E. 57.50'  
 Maple 3" S. 23° W. 69.60'  
 Maple 18" S. 18° E. 99.80'
  - 1996: Found 3/4" x 18" iron bar over tile with cross in top 30" deep in monument box.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
5-16-1996

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- K-07: Southeast corner Section 14, T. 1 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 16, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with cross on top as set by F. Hodgman, County Surveyor in a remonumentation survey in 1887 inside a monument box. Set 20" Harrison Monument over tile in monument box.  
 PK Nail on East Side 22" Walnut N. 30° W. 46.10'  
 PK Nail on East Side 24" Walnut N. 20° W. 30.17'  
 PK Nail on East Side 10" Ash S. 36° E. 50.44'  
 PK Nail on North Side 28" Maple S. 30° W. 69.00'

Signed by Robert E. Snell Date 5-23-96