

3

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

'94 MAR 17 PM 3 39

For corners in RICHLAND TWP.

<u>KALAMAZOO</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>1</u> SR <u>10</u> W	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*James [Signature]*  
CLERK-REGISTER

LIBER **1** PG **1126**

Register of Deeds Stamp & File Number

I, Allen H. McMachen a field survey on February 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1880's - F. Hodgeman C.S. placed Clay Tile Post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile (at "T" iron fence post)

*R. E. [Signature]*  
**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
3-3-94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Standard Sleeve over existing Clay Tile, Accessories:

- Nail & Tab in West face                      30" Oak            NORTH 20.53'
- Nail & Tab in East face                      6" Oak N. 23 deg. W. 32.99'
- Nail & Tab in South face                      10" Oak N. 35 deg. W. 67.69'
- Nail & Tab in North face                      42" Cherry N. 85 deg. W. 26.23'

Signed by Allen H. McMachen Date 3/15/94  
Surveyor's Michigan License No. 16935