

1  
2

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970'94 APR 28 AM 9 11

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Sec. 25, Richland Twp.

1. Public Land Survey

T 1 S R 10 W

K-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*James J. [Signature]*

CLERK-REGISTER

LIBER 1 PG 1134

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Robert E. Snell, in a field survey on February 25, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner placed by U.S. Government Survey-Set Post, corner to Sections 25, 26, 35, and 36

Wh. Oak 36" South 88° East 105 Lks

Wh. Oak 9" South 61½ West 112 Lks

1887-F.Hodgeman, County Surveyor-Set post in angle of fence 47 Lks from Hickory and 156 Lks from Poplar Bearing Trees noted by F.Stimson, County Surveyor-now standing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3" round tile with "X" on top from LCRC witness (1989)

*[Signature]*  
RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 Southwest Corner Section 25, T. 1 S., R. 10 W., ratified by Kalamazoo Remonumentation Program Peer Group on April 21, 1994. Found 3" round tile with "X" on top as called for in 1887 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

Tree Line		North	160.00'
PK Nail in	6" Hickory	North 30° East	61.12'
PK Nail	6" Apple	North 45° East	31.85'
Irrigation Water Valve		East	2.64'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 4-26-94