

JUL 28 1997

1 COMMISSION

LIBER

2 PAGE 146

2- 1474

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.

Kalamazoo

(County)

Located In:

Corner Code #

1. Public Land Survey	T 1 S	R 10 W	L-06
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

CLERK - REGISTER

James J. Howard

97 JUN 24 PM 1 17

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on March 27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

This corner not established by original Government Surveyors.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-17-1997 *R.E.S.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Ran North and South 1/4 line and East and West 1/4 line to re-establish corner. Corner placed at intersection of 1/4 lines. This center 1/4 post was established in 1957 by Wilkins & Wheaton Engr. Co., by intersecting 1/4 lines. Corner removed during reconstruction of road intersection in 1994.

Distances: East 1/4 post to center = 2,632.5'
West 1/4 post to center = 2,640.3'
North 1/4 post to center = 2,640.72'
South 1/4 post to center = 2,647.67'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-06: Center of Section 13, T. 1 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group as a careful and faithful establishment of the position of the corner. This corner not established by original Government Surveyors. Placed 20" Harrison Monument in monument box, 33' West of intersection of 35th Street and "CD" Avenue. Ratified April 17, 1997.

PK Nail in East Side	22" Maple	N. 26° W.	58.57'
PK Nail in East Side	10" Cedar	S. 10° W.	56.45'
PK Nail in North Side	Power Pole	S. 50° E.	91.19'
Center line	"CD" Avenue	South	3.0'

Signed by *Robert E. Snell*

Date 6-17-97

Surveyor's Michigan License No. 9734