

'94 APR 28 AM 9 12

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Sec. 13, Richland Twp.

1. Public Land Survey

T 1 S R 10 W

L-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

James J. Prop

CLERK - REGISTER

LIBER

1 PG 1150

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on March 1, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner established by U.S. Government Survey-Set $\frac{1}{2}$ Section Post.

Wh. Oak 16" South 77° East 75 Lks

Wh. Oak 7" North 47° East 130 Lks

1887-F. Hodgeman, County Surveyor-Found old stake with brick beside in edge of pond,

North 52° West, 118½ Lks from stump of Bearing Tree of resurvey by Stimson. Set Post.

Hickory 8" South 83½° East 148 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile under 1'± of water.

R. E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 South $\frac{1}{2}$ Post Section 13, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found 3" round tile under 1'± of water at edge of pond as called for in 1887 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

Concrete Survey Monument		East	14.80'
PK Nail in South Side	12" Pine	North 45° East	74.00'
PK Nail in North Side	8" W. Cherry	North 76° East	63.45'
PK Nail in North Side	14" Pine	North 82° East	70.10'
"T" Iron	Fence Post	North	0.30'

Signed by

Robert E. Snell

Date

4-27-94

Surveyor's Michigan License No.

9734