

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Kalamazoo

(County)

Located In:

Corner Code #

Richland Section 25

- |                                    |                            |            |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey              | T <u>1</u> S R <u>10</u> W | <u>L-9</u> |
|                                    | T _____ R _____            | _____      |
|                                    | T _____ R _____            | _____      |
|                                    | T _____ R _____            | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____      |
|                                    | S _____ T _____ R _____    | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____      |
|                                    | S _____ T _____ R _____    | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 94 MAR 15 PM 1 37  
 Clerk - Register  
*Jessie J. [Signature]*

LIBER 1 PG 1106  
 Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on February 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by U.S. Government Survey of 1826-Set Post.

- Wh. Oak 8" South 32°-W 16 Lks (10.56')
- Wh. Oak 7" North 55°-E 18 Lks (11.88')

1870-F. Hodgeman County Surveyor-1/4 Section corner stake and stone and one witness standing.

1887-F. Hodgeman-found stake and of former survey South 55°-W 18 Lks (11.88") from where bearing tree was dug out. Set Post.

- Wh. Oak 8" North 31 Lks (20.46')
- Hickory 4" South 52½°-E 30 Lks (20.13')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" clay tile down 4"±

*R.E.S.*  
**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 3-3-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 North 1/4 Post Section 25, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" round tile ("X" on top) as called for in 1887 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed remonumentation sleeve over tile with Iron on South side of tile/sleeve.

- PK Nail in S side 12" Oak North 36°-W 4.29'
- PK Nail in S side Db1.12" Hickory North 70°-W 10.02'
- Exist.Nail/Tab in E side 15' Oak North 38.71'
- PK Nail in W side 11" Oak South 20°-E 20.42'
- In line with centerline of road to West and 7.0' West of centerline of bituminous drive.

Signed by *Robert E. Snell* Date 3-15-94  
 Surveyor's Michigan License No. 9734