

7  
2

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

'94 APR 28 AM 9 11

For corners in

KALAMAZOO  
(County)

Located In:

Corner Code #

*James J. [Signature]*

CLERK-REGISTER

Sec. 25, Richland Twp.  
 1. Public Land Survey

T 1 S R 10 W

L-11

- 2. Property Controlling in Section
- 3. Miscellaneous
- Property in Sec.

S T R  
 S T R  
 S T R  
 S T R

LIBER 1 PG 1136

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on February 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner established by U.S. Government Survey-Set 1/4 Section Post.

- Wh. Oak 10" North 19° East 62 Lks
- Wh. Oak 16" South 22° East 10 Lks

1887-F. Hodgeman, County Surveyor-Found old stake in angle of fence, South 19° West, 62 Lks from Wh. Oak Bearing Tree standing. Set Post.

Hickory 8" South about 75° East 13 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile with "X" on top.

*[Signature]*  
**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 South 1/4 Post Section 25, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found 3" round clay tile with "X" on top as called for in 1887 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

Fences, North, South, East, and West-In Line from Point

- PK Nail in 15" Walnut North 05° West 12.90'
- PK Nail in 10" W.Cherry East 25.55'
- PK Nail in 16" W.Cherry South 30° West 92.79'

Signed by

*Robert E. Snell*

Date

4-26-94

Surveyor's Michigan License No.

9734