

SURVEY & REMONUMENTATION

1
2

APR 27 1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 4 DEC 15 PM 1 36

For corners in **Richland Twp.**

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>1S</u> R <u>10W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. Jones
CLERK-REGISTER

LIBER 1 PG 1217

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen a field surveyor on June 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1880's - F. Hodgeman C.S. placed Clay Tile Post during official Township Remonumentation.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Clay Tile at intersection of North - South fence with fence running West.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
7/21/94
R.H.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Standard Sleeve over existing Tile, Accessories:

- Nail & Tab in W. side 20" Hickory N. 05° W. 7.65'
- Nail & Tab in N. side 16" Ash N. 85° W. 15.74'
- Nail & Tab in E. side 8" Cherry South 15.62'
- Nail & Tab in E. side 12" Quad Ash S. 05° E. 32.65'

Signed by *Allen H. McMachen* Date 11/17/94
Surveyor's Michigan License No. 16935