

'95 SEP 25 PM 1 15

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
 Kalamazoo

(County)	Located In:	Corner Code #
1. Public Land Survey	T 1 S. R 10 W.	M8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*James Jensen*  
 CLERK-REGISTER

LIBER 1 1353

Register of Deeds Stamp & File Number

4. Lot No. N/A, Recorded Plat N/A  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GREGORY N. JENSEN, in a field survey on 4/7/95, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

a- SET POST 1826 GLO SURVEY, BUTTERNUT NE. 110 LINKS (72.6')

F. HODGEMAN COUNTY SURVEYOR, FOUND STAKE & STONE OF RESURVEY & BUTTERNUT BRG. TREE STANDING NE. 110 LINKS (72.6')  
 SET POST (CLAY TILE) WITH W/ STONE AROUND  
 JUNIPER 2' S 22' W, 48 LINKS (31.68')  
 CHERRY 8' N 41' W, 70 LINKS (46.2')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

b- M8 EAST 1/4 POST SECTION 24, T.1 S., R.10 W.  
 FOUND SOLID CLAY TILE W/ CROSS IN MONUMENT BOX

**RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP**

*7-23-95  
 8-10-95 J.C.S. R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

c- M8 EAST 1/4 POST SECTION 24, T.1 S., R.10 W., RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PROGRAM PEER GROUP ON JULY 23, 1995. FOUND CLAY TILE CALLED FOR BY F. HODGEMAN COUNTY SURVEYOR AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. PLACED REMONUMENTATION SLEEVE OVER TILE.

- 16" WALNUT, NE. 33.28'
- POWER POLE, SE. 41.26'
- 11" MAPLE, SW. 28.64'
- 26" OAK, NW. 46.05'



Signed by *Gregory N. Jensen*  
 Surveyor's Michigan License No. 31593

Date 9/11/95