

**SURVEY & REMONUMENTATION**

OCT 06 1997

LIBER 2 PAGE 180

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Richland Twp.  
Kalamazoo Located In: Corner Code #  
 (County)

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>M-9</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 1997 JUL 29 PM 3 57  
 Clerk - Register  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 4, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1826 - John Mullett, D.S.  
Set post corner to Sections 24 & 25, Wh. Ash 9" S. 5 1/2° W. 215 lks., Bl. Oak 10" N. 72° W. 192 lks.
  - 1887 - F. Hodgman, C.S., "Found fence post on corner S 72 3/4° E. 193 lks. from Elm bearing tree of resurvey and 128 lks. South and 8 lks. West of Ross corner."
  - 1991 - Chettleburgh & Assoc., Records Survey L. 2, Pg. 117, 3" Clay Tile, 12" Willow NNE 83.83', 13" Oak SE 58.91', 17" Oak SE 90.76', Mult Willow W. 111.65'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 Found clay tile in marsh being held vertical by 3 pipes driven in along side.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:  
 Nail & Tab in West side 18" Willow N. 05° E. 83.93'  
 Nail & Tab in South side 4" Poplar East 2.6'  
 Nail & Tab in East side 22" Ash S. 25° W. 121.45'  
 Nail & Tab in South side 5" Poplar West 11.9'

**RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP**  
 6-19-1997  
*R.E.C.*



Signed by Allen H. McMachen  
 Surveyor's Michigan License No. 16935

Date 7/14/97