

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

94 APR 28 AM 9 12

For corners in

KALAMAZOO
 (County)

Located In:

Corner Code #

Sec. 25, Richland Twp.
 1. Public Land Survey

T 1 S R 10 W

M-10

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

James J. Jones
 CLERK - REGISTER

LIBER

1 PG 1148

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Snell, in a field survey on March 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825-Original corner established by U.S. Government Survey-Set $\frac{1}{4}$ Section Post.

Wh. Oak 12" South $28\frac{1}{2}^\circ$ West 38 Lks

Wh. Oak 18" North $05\frac{1}{2}^\circ$ West 135 Lks

1887-F. Hodgeman, County Surveyor-found old stake North $28\frac{1}{2}^\circ$ East, 38 Lks from stump of Wh. Oak Bearing Tree. Set Post.

Wh. Oak 8" South 24° East 21 $\frac{1}{2}$ Lks

This is about half a rod west of North and South fence as it now stands.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile with "X" on top.

R. E. Snell
 RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 East $\frac{1}{4}$ Post Section 25, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found solid clay (3" Dia.) with "X" on top as called for in 1887 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

North and South Fence East 7.0'
 PK Nail in 12" Oak East 30.80'
 PK Nail in 26" Oak South 10° West 10.30'
 PK Nail in 12" Hickory South 40° West 5.84'

Signed by *Robert E. Snell* Date 4-27-94
 Surveyor's Michigan License No. 9734