

SURVEY & REMONUMENTATION

16935

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'95 AUG 24 PM 3 58

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COOPER TOWNSHIP  
KALAMAZOO (County)

Located In: Corner Code #

1. Public Land Survey	T	1	S	R	11	W	A-7
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Section	S		T		R		
	S		T		R		

*James [Signature]*  
CLERK-REGISTER

LIBER 1 1319

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Allen H. McMachen a field survey on April 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
  - 1826 - John Mullett, D.S. Intersected West Boundary 40 lks. North of post, Set Post at Intersection cor. to Sec.'s 18 & 19 Wh. Oak 6" S. 59° E. 19 lks. Wh. Oak 7" N. 08° E. 20 lks.
  - 1904 - E. Strong, C.S. Stone & Brick B. Oak 4" N. 60° ? W. 48½ lks. B. Oak W. 2° S. 96½ lks.
  - 1923 - Kal. Co. Rd. Comm. Found Stone, Also Found Stone 26.4' South (S.E. Cor., Sec. 13, Alamo Township)
  - 1953 - Kal. Co. Rd. Comm. Found Stone 18" deep, placed 12" Iron over. U.S.G.S. Benchmark N. 80° W. 25'-7" 20" Maple S. 45° W. 62'-1"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 5/8" Iron rod in 2½" ring + 3" below surface, removed iron and found second 5/8" Iron 2' below surface, removed and found large rounded Stone 3' below surface. Stone has a notch in top, and notch fits first 5/8" Iron found. Found Iron in Mon. box South 26.82' (N.E. Cor., Sec. 24, Alamo Twp.)

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
4-20-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Found Stone with notch is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over found Stone and Monument box over. Accessories:

- "PK" Nail & Tab in S.W. Side U. Pole N. 86° E. 34.52'
- "PK" Nail & Tab (± 4' above ground) in U. Pole S. 48° W. 101.92'
- "PK" Nail & Tab (± 4' above ground) in U. Pole S. 32° E. 82.57'
- Nail & Tab in 16" Walnut N. 54° W. 32.32'

Signed by *Allen H. McMachen*

Date 5/24/95

Surveyor's Michigan License No. 16935