

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'95 DEC 14 PM 3 30

For corners in Cooper Township  
Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>11W.</u>	<u>A-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

*James D. Young*  
CLERK-REGISTER

LIBER **1 1410**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_
- 6. IWM Job No. 24971

A	B	C	D	E	F	G	H	J	K	L	M
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Allen H. McMachen, in a field survey on April 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner not set by original Government Surveyors  
1923 - Kalamazoo County Road Commission found stone  
6" Oak N. 72° E. 26.0'  
24" Maple S. 43½° W. 40.0'

Road Commission also found stones at N.W. and S.W. corners of Section 19, Cooper Township and they measured between them at 5314.5'. Road Commission also measured from stone at N.W. corner, Section 19 to stone at W.¼ corner, Section 19 at 2656.7'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Ingersoll, Watson & McMachen, Inc. prorated its mile to the Kalamazoo County Road Commission information and excavated to depth of about 6' and found nothing. IWM placed iron at prorated mile distance being 2652.35' South of stone at N.W. corner, Section 19 and 2653.44' North of stone at S.W. corner, Section 19. Also measured South from iron placed at W.¼ cor., Section 19 to iron found at E.¼ corner, Section 24, Alamo Township at 23.7' (Government 23.1').

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
7-20-95 *[Signature]*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

This position not established by original Government Surveyors. Iron placed is accepted as the best available evidence of the position of the corner. Removed iron rod and placed Harrison Monument and Mon. Box., Accessories:

- Nail & Tab in N.W. face 16" Oak N. 27° E., 49.76'
- Nail & Tab in N.E. face 12" Hickory S. 30° E. 67.76'
- Nail & Tab in North face 10" Maple S. 50° W. 39.70'
- Nail & Tab in North face 14" Maple N. 80° W. 76.08'



Signed by *Allen H. McMachen*  
Surveyor's Michigan License No. 16935

Date 12/13/95