

NOV 1983

CO. 1

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COOPER TOWNSHIP

KALAMAZOO
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S 11 R 11 W A-9
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Section S T R
S T R

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 AUG 24 PM 3 58

James J. Jones

CLERK-REGISTER

LIBER

1 1318

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen field survey on April 4, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 - John Mullett, D.S. 1940 - Wilkins & Wheaton
Intersect West Boundary 30 lks. Found Stone, Brought up
North of post, Set Post at with Iron
Intersection cor. to Sec.'s 19 & 30 40" Oak S. 70° E. 34.32'
Wh. Oak 8" S. 04° E. 19 lks. 6" Oak N. 30° E. 44.43'
Wh. Oak 12" N. 56° E. 29 lks. 8" Hick. S. 60° W. 58.9'
1909 - E. Strong, C.S. 4" Hick. N. 50° E. 83.2'
Found Stone B. Oak 25" S. 70° E. 52 lks.
1920 - Kal. Co. Rd. Comm. (S.E. Cor., Sec. 24,
Found Stone, Also Found Stone 20' South Alamo Township)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron rod 3" below surface, removed Iron and found 5/8" Iron below 0.15' North and 0.05' East of 1/2" Iron. Removed 5/8" Iron and found pointed stone with drill hole 3' below surface. Stone is 0.04' South & 0.12" West of 1/2" Iron location. Also found Stone 19.40' South (S.E. Cor., Sec. 24, Alamo Township.) (Gov't 19.8').

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-20-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Drilled Stone is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over found Stone and Monument box over. Accessories:

- Nail & Tab in S.E. Side 6" Maple N. 44° E. 51.17'
- Nail & Tab in S.W. Side 8" Oak S. 38° E. 58.06'
- Nail & Tab in N. Side 26" Hick. S. 48° W. 69.66'
- Chiseled "X" in North End Conc. Culvert N. 70° E. 53.30'

Signed by

Allen H. McMachen
16935

Date

5/24/95

Surveyor's Michigan License No.