

MAY 16 1996

COMMISSION

LIBER

1 PAGE 1466

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cooper Township
Kalamazoo (County)

Located In:

Corner Code #

Table with 3 columns: Description (Public Land Survey, Property Controlling, etc.), Located In (T, S, R), and Corner Code # (B-9).

Register of Deeds Stamp & File Number. Includes signature of Clerk-Register and date 96 APR 19 AM 10 30.

- 4. Lot No.
5. Private Claims
6. IWM Job #'s 24071, 24991, 27425, 27585

I, Allen H. McMachen, in a field survey on January, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at row 9, column C.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - John Mullet, set quarter Section post
W. Oak 18" S. 13° W. 9 lks., W. Oak 10" N. 02° W. 41 lks.
1940 - Wilkins & Wheaton, iron in North fence line
20" B. Walnut N. 2° E. 48.85'
8" Hickory S. 20° W. 22.56'
10" Oak N. 40° W. 49.64'
2" B. Walnut S. 60° E. 72.6'
Centerline road 5.5' North
1973 - Ingersoll, Watson & McMachen
Record corner L.C.R.C. L. 1 Pg. 251
Iron in North fence line
Centerline road 5.5' North
10" Oak N. 40° W. 49.64'
20" Walnut N. 02° E. 48.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in monument box ±7" South of center line "E" Avenue, excavated extensively for additional marker but found none. Measured East to stone at SE corner @2652.34' (1940 Wilkins = 2652.6'). Iron is very near a straight line extended Westerly between found iron at S 1/8 cor., SE 1/4 (per 1940 Wilkins notes) and stone at SE corner.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 2-15-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found iron in monument box is accepted as the best available evidence of the position of the corner. Placed Harrison Monument in place of found iron & placed mon. box over, accessories:

- Nail & Tab in E. side 30" Walnut North 50.34'
Nail & Tab in E. side 12" Cherry S. 25° E. 23.27'
Nail & Tab in NW side 12" Cherry S. 45° W. 30.74'
Nail & Tab in E. side 24" Oak N. 50° W. 49.64'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 4/16/96

