

SURVEY & REMONUMENTATION

1 FEB 26 1998

2 SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Cooper Township		
1. Public Land Survey	T <u>1</u> S R <u>11</u> W	<u>C-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 DEC 22 AM 8 59
CLERK - REGISTER
LIBER 2 PAGE 257
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William K. Crane, in a field survey on May 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	●	5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1827. John Mullett. DS:
16" W. Oak S 8° E 42 links
14" Y. Oak N 20° W 28 links

F. Hodgman. 1870. County Surveyor Records. Volume I:
Found stone set for 1/4 Sec Corner

LCRC. Liber 1. Page 725. by Allen H. McMachen:
Stone
24" Oak S 50° W 40.21'
Fen. Cor. South 32.1'
20" Cherry S 35° E 37.3'
U.P. N 55° E 27.7'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-19-1997

R. E. S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone with "x" in monument box. Dug 2.5 feet, found pieces of crockery and scrap metal. Replaced stone with Harrison monument and reset monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone with "x" is accepted as a careful and faithful perpetuation of the position of the original corner. Replaced stone with Harrison monument and reset monument box.

Set nail NW side 4" Hickory S 32° W 32.38'
Set nail SE side 4" Hickory S 73° W 69.94'
Found nail SE side of U. Pole N 57° E 26.69'
Set PK nail W side U. Pole S 05° E 35.21'

Signed by William K. Crane

William K. Crane, P.S.

Date December 22, 1997

Surveyor's Michigan License No. 29243