

SURVEY & REMONUMENTATION

7- MAY 28 1997
2 COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SEP 9 PM 3 51

For corners in Cooper Township
Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	1S.	R	11W.	C-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

James Young
CLERK - REGISTER

LIBER 2 PAGE 059

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job Nos. 24071, 24991, 27425 & 27585

I, Allen H. McMachen, in a field survey on January, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <u>1827</u> - John Mullet, D.S.
Set 1/4 Section post
W. Oak 12" N. 17° 27 lks
Y. Oak 14" S. 19° W., 24 lks. | <u>1940</u> - County Surveyor
Placed iron on bi-section
(2652.2' S. of Northeast corner)
14" Maple West 19.95'
24" Maple S. 60° W. 27.88'
Fence East 22.5'
8" W. Cherry S. 20° E. 96.4' |
| <u>1931</u> - Kal. Co. Road Commission
Found brick, set iron-stake on top
15" Maple S. 89° W. 20.55'
24" Maple S. 45° W. 29.10'
Pole #7585 N. 35° E. 39.2' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in mon. box nearly on line between Northeast corner and Southeast corner and nearly midway between said corners. Iron also matches (2) of the 1940 witnesses

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-15-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron is accepted as a careful and faithful reestablishment of the position of the original corner. Removed 1/2" iron and replaced with Harrison Monument in mon. box, Accessories:

- Nail & Tab in S. Side U. Pole N. 80° E. 37.75'
- Nail & Tab in SW side 6" tulip S. 55° E. 44.12'
- Nail & Tab in North Side 42" Maple S. 44° W. 28.23' (1940 wit.)
- Nail & Tab in North side 36" Maple West 19.42'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 9/6/96