

SURVEY & REMONUMENTATION

MAY 16 1996

COMMISSION

LIBER

1 PAGE 1468

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cooper Township
Kalamazoo
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>11W.</u>	<u>C-9</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		R		
	S		R		
3. Miscellaneous	S		R		
Property in Section	S		R		

CLERK - REGISTER

[Signature]

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '96 APR 19 AM 10 30

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 6. IWM Job #'s 24071, 24991, 27425, 27585

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - John Mullet, set post corner to Secs. 19, 20, 29 & 30
 W. Oak 9" S. 33° W. 94 lks., W. Oak 9" N. 40° E. 12 lks.
- 1931 - Kalamazoo County Road Commission
 Found stone, brick & rubbish by Wheaton, also base of old stake 1' West, set iron on old stake
 18" Walnut N. 50° W. 40.4'
 15" Walnut N 70° E. 54.45'
 18" Cherry S. 45° W. 42.6'

- 1940 - Wilkins & Wheaton
 Found stone & brick 2' below, brought up with iron
 20" Walnut N. 45° W. 41.0'
 18" Walnut N. 45° E. 54.0'
 20" Cherry S. 45° W. 42.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron 6" below road surface, removed iron, excavated and found a 6" X 8" X 6" stone in ring of brick & cinders, 2.5' below road surface. Also found 3/4" iron at same depth as stone and ±0.5' West of stone. Stone is 0.25' West and 0.25' North of found 1/2" iron. Measured from stone to iron at S. 1/8 cor., SE 1/4 (believed to be placed by Wilkins & Wheaton in 1940, matching one previous witness) at 1326.17' (1940 Wilkins & Wheaton = 1326.3') and line between stone at SE corner and iron at S 1/4 corner is 0.1' North of said found 1/8 corner.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 2-15-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone is accepted as the best available evidence of the position of the corner. Placed Harrison Monument over found stone with monument box over, Accessories:

- Nail & Tab in utility pole N. 43° W., 81.49'
- Nail & Tab in utility pole N. 30° E. 64.95'
- NW corner of garage (#3166) S. 47° E. 122.20'
- NE corner of metal barn S. 65° W. 100.39'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 4/16/96
 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983