

**SURVEY & REMONUMENTATION**

1  
2  
SEP 14 1998

**SECTION**

For corners in Cooper Twp.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 315

CLERK - REGISTER

*Handwritten signature*

98 SEP 3 PM 3 25

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T 1 S R 11 W	D-09
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on April 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		29	28	27	26	25						
10	30											
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1826: United States Government Surveyors; set 1/4 post.  
White Oak 16" S. 70° W. 15 lks.  
Yellow Oak 26" East 17 lks.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
5-21-1998  
*R.E.S.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1946: Wilkins & Wheaton Engr. Co.; found brick and placed iron.  
36" Locust N. 40° E. 33.5'  
Telephone Pole S. 50° W. 50.0'  
Fence Intersection S. 5° W. 33.3'  
1976: Al McMachen, RLS #16935; LCRC L-1, P-722; 3/4" iron.  
36" Locust N. 40° E. 33.50'  
Telephone Pole S. 50° W. 50.00'  
Fence Corner S. 5° W. 33.30'  
1998: Found 1/2" x 2 ft. iron in monument box. Brick scattered around to 3 ft. to 3 1/2 ft. in all directions from iron. Greatest concentration within 6"-8" of iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
D-09: South 1/4 post, Section 20, T. 1 S., R. 11 W., ratified on May 21, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as the best available evidence of the position of the original corner. Found 1/2" x 2 ft. iron rod with brick around as placed in 1946 survey by Wilkins & Wheaton Engr. Co., County Surveyor, in monument box. Placed 20" Harrison monument in new monument box.  
Old Nail/Tab in East Side 36" Locust N. 40° E. 33.46'  
PK Nail in West Side Double Maple S. 20° E. 40.05'  
PK Nail in North Side Telephone Pole S. 60° W. 49.76'  
PK Nail in East Side 34" Locust N. 28° W. 36.24'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 9-2-98