

**SURVEY &  
REMONUMENTATION**

FEB 26 1998

1  
2

SECTION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Cooper Township		
1. Public Land Survey	T <u>1S</u> R <u>11W</u>	<u>F-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 DEC 22 AM 8 59  
J. J. [Signature]  
CLERK - REGISTER  
LIBER 2 PAGE 258

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on May 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5					●							
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1827, John Mullett, DS:  
18" W. Oak N 40° E 229 links  
18" D.O. S 38° W 299 links

County Surveyor Notes, E. Strong, April 15, 1908:  
N 1/4 Corner, Section 18  
8" Cedar N 40° E 105 links  
12" Apple N 45° W 107 1/2 links

E. Strong, May 17, 1909:  
Found brick and iron  
8" Elm N 2° E 0.25 chains  
8" Elm East 0.14 chains

LCRC Liber 1, Page 798 by David Peabody:  
Monument Box  
6" Maple N 50° E 59.5'  
30" Mulberry N 30° E 90.8'  
In C/L road  
Utility Pole S 30° W 60.0'

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
6-19-1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Removed 5/8" iron rod and monument box, dug 2'± and found stone with "x" at top and a plow point standing vertical beside stone. Replaced stone with Harrison monument and reset monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found stone with "x" is accepted as a careful and faithful perpetuation of the position of the original corner. Replaced stone with Harrison monument and reset monument box.

Utility pole S 71° E 176.89'  
24" Walnut N 08° E 143.30'  
Utility pole S 22° W 60.24'  
20" Twin cherry S 84° W 217.17'

Signed by William K. Crane  
William K. Crane, P.S.  
Surveyor's Michigan License No. 29243

Date December 22, 1997