

FEB 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo Located In: Corner Code #
 (County)
 Cooper Township
 1. Public Land Survey T 1 S R 11 W F-7
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William K. Crane, in a field survey on September 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O., John Mullett, D.S., 1827:
14" W. Oak S 8° W 25 links
18" W. Oak N 8° E 28 links
 - E. Strong, October, 1873:
Iron, brick & stone of former survey
 - E. Strong, May, 1909:
Found stone, brick & iron of Albertson
8" Elm N 2° E .25
Elm East .14
 - Kalamazoo County Road Commission:
12" W. Cherry S 30° W 37.1'
20" Maple S 25° E 30.3'
24" Maple N 80° E 60.5'
24" Maple N 30° E 59.3'

LCRC, Watson, 11/26/71:
 Iron rod
 20" Maple S 25° E 30.3'
 24" Maple N 80° E 60.5'
 24" Maple N 30° E 59.3'
 12" W. Cherry S 30° W 37.1'

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 5-4-1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found large spike in 2" x 3" long pipe, removed and found 3/4" iron rod, removed and dug 2.5 feet, found brick with pieces of scrap iron. Replaced irons with Harrison monument and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" iron rod is accepted as the best available evidence of the position of the original corner. Replaced iron with Harrison monument and set monument box.

36" Cherry S 54° W 37.84'
 36" Walnut S 70° E 95.76'
 26" Maple N 20° E 82.86'
 6" x 6" Corner Post South 32.36'

Signed by William K. Crane Date July 12, 1999
 William K. Crane, P.S.
 Surveyor's Michigan License No. 29243

