

APR 01 1996

96 JAN 23 PM 3 50

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Kalamazoo
(County)
Cooper Twp.

Located In:

Corner Code #

1. Public Land Survey	T <u>1 S.</u> R <u>11 W.</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James P. Young
CLERK-REGISTER

LIBER **1 1432**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on October 25, 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1826: United States Government Surveyors; set 1/4 Section post.
 Elm 8" S. 82° E. 56 lks.
 W. Ash 18" N. 89° W. 39 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1995: Found 4" iron pipe in concrete with brass cap, cap reads KVP 1950 S 1/4 Post Sec. 34 BM#41 755.72. Cap is 1' above surface leaning 0.35'+ East of perpendicular, in causeway to river. Monument is very solidly in place. From Southeast corner Section 34, T. 1 S., R. 11 W is measures 2,653.56' to monument.

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 12-14-95
R. E. Snell
 Brass cap retained
 35 Mon.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H-13: South 1/4 post to Section 34, T. 1 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 14, 1995 and is accepted as the best available evidence of the position of the original corner. Found 4" iron post with brass cap.

Double Head Nail in East Side	7" Box Elder	N. 24° W.	1.98'
Double Head Nail in South Side	14" Maple	East	20.30'
Double Head Nail in West Side	20" Maple (Dead)	S. 25° E.	41.61'
PK Nail in North Side	9" Sycamore	S. 82° W.	32.23'

Signed by *Robert E. Snell*

Date 1-18-96

Surveyor's Michigan License No. 9734