

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 085

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #
Cooper ^(County) Twp.		
1. Public Land Survey	T 1 S R 11 W	I-07
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1996 NOV 15 PM 1 59
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Sept. 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; set post, corner to Sections 14, 15, 22 & 23.
W. Oak 7" S. 12° W. 17 lks.
Elm 10" N. 50° W. 9 lks.
- 1869: F. Hodgman, County Surveyor; ...I then went to Southeast corner of Section 15 and found the point of the stake and set a stone 12" x 10" x 8" in its place."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1949: Wilkins & Wheaton Engr. Co.; found stone and set iron over.
30" Maple North 103.64' 12" Elm S. 60° E. 67.9'
8" Elm S. 15° E. 126.35' In fence line to North
Fence to South - West 1.5'
- 1972: Don Gilchrist, RLS #13583; recorded L.C.R.C., L-1, P-33, found iron in monument box.
Iron in fence line North and South and center line of road.
Power Pole N. 30° E. 34.68' Nail/Tab 14" Apple S. 45° W. 60.14'
Fence corner South 34.0
- 1996: Found Railroad spike in monument box between two pieces of broken cap of box 1" x 12" iron pipe below. At a distance of 2.58' East and down 3' found stone (12"x10"x8") with drill mark and 1/2" x 18" iron rod over stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-07: Southwest corner Section 14, T. 1 S., R. 11 W.; ratified by Kalamazoo County Remonumentation Program Peer Group on October 17, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 12" x 10" x 8" stone as called for in 1869 survey by F. Hodgman, County Surveyor, with 1/2" x 18" iron rod over it. Placed 20" Harrison Monument in Monument Box over stone.
- | | | | |
|-------------------------------------|----------------|-----------|---------|
| PK Nail in East Side | 36" Maple | North | 109.55' |
| PK Nail in East Side | Power Pole | N. 40° E. | 34.19' |
| PK Nail over Nail/Flag in West Side | 15" DbL. Maple | S. 30° E. | 53.99' |
| PK Nail over Nail/Flag in West Side | 8" W. Pine | S. 12° W. | 37.19' |

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 11-14-96