

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #
Cooper ^(County) Twp.		
1. Public Land Survey	T <u>1S</u> R <u>11W</u>	<u>1-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 25 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set post, corner to Sections 34 & 35.

W. Oak 18" N. 71° E. 117 lks.
W. Oak 20" N. 49° W. 63 lks.

1865: M. Stimson, Deputy County Surveyor; set stake 14 lks. West of corner to Sections 2 & 3, Kalamazoo. The Kalamazoo corner corresponded (by) course & distance with field notes of witness one stump only standing - mark visible ... Cooper corner did not correspond exactly.

1884: F. Hodgman, County Surveyor; found Kalamazoo corner 14 lks. East of Cooper corner stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

1923, 1939: Wilkins & Wheaton Engr. Co.; field notes show Southeast corner but do not describe it.

1996: Found stone (9" x 9" x 9" x 28") triangular stone with drill mark in middle 9.37' West of tile for Kalamazoo corner.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-20-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-13: Southeast corner Section 34, T. 1 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on June 20, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found triangular stone with drill mark 9.37' West of tile as noted in 1884 remonumentation survey by F. Hodgman, County Surveyor. Removed stone and placed 20" Harrison monument in monument box. Double head nail in North side 10" Ash N. 54° W., 78.24'

PK Nail in East Side	Guy Pole	S. 36° E.	29.55'
PK Nail in North Side	30" Oak	N. 80° E.	103.53'
PK Nail in East Side	Power Pole	N. 50° E.	34.34'
Double Head Nail in West Side	19" Elm	S. 30° W.	34.38'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 10-14-96