

**SURVEY &
REMONUMENTATION**

7
2

APR 27 1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 DEC 15 PM 1 36

For corners in COOPER TWP.

KALAMAZOO Located In: Corner Code #
(County)

1. Public Land Survey T 1 S R 11 W J-5
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

J. J. J.
CLERK - REGISTER

LIBER 1 PG 1220

Register of Deeds Stamp & File Number

I, Allen H. McMachen a field survey on January 30, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Government - Lynn 6" N. 15° W. 12 lks.
Lynn 6" S. 33° E. 21 lks.
No additional information found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed Stone 1.0' below surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed Stone is accepted as a careful and faithful perpetuation of original corner. Removed Stone and placed Harrison monument.
Accessories:

S.W. corner Co. Po. Co. tower N. 77° E. 115.40'
Angle Iron at surface of concrete SOUTH 8.10'
Angle Iron at surface of concrete S. 65° W. 16.98'
Set Iron rod with cap N. 82° W. 76.56'
Center line E. & W. drainage ditch NORTH 21'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-17-94 *R. E. G.*



Signed by *Allen H. McMachen* Date 12/15/94
Surveyor's Michigan License No. 16935

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													