

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSION

LIBER 2 PAGE 121

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cooper Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T1S R11W	J-07
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1997 APR 7 AM 9 22
Clerk - Register
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Sept. 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 2-27-1997

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 Section post.

Blk. Oak 7" S. 81° E. 10 lks.
Blk. Oak 5" S. 41° W. 22 lks.

1888: E. Strong, County Surveyor; "N 1/4 (Sec. 23) John Albertson says it is 5 P (?) East of Bridge and in N. Wagon Tra(ck)" No mention of what was set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1972: Donald Gilchrist, RLS #13583; L.C.R.C. L-1, P-33, found iron in monument box set by Don R. Gilchrist in 1967 on split of distance 13' West of fence line to North and South 12" Ash N. 45° W., 40.26', 6" Ash S. 40° W., 47.26', 48' East of center line creek.

1980: Wilkins & Wheaton used iron in monument box.

& 1994:

1996: Found iron in monument box. 2.28' East and 1.15' North found pieces of iron with pieces of glass, vitrified clay, pottery, and 1"x2" wood stake in old Corduroy Road at a depth of about 4 1/2'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-09: South 1/4 post Section 14, T. 1 S., R. 11 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on February 27, 1997 and is accepted as the best available evidence of the position of the original corner. Found pieces of iron, glass, vitrified clay, pottery and 1"x2" wood stake believed to be corner mentioned in 1888 survey by Ed Strong, County Surveyor. Placed 20" Harrison monument over wood stake/iron in monument box.

Center line of new Road Culvert
PK Nail in East Side 15" Ash
PK Nail in North Side 4" Ash
PK Nail in East Side 7" Ash
PK Nail in West Side 20" Ash

West 48.8'
N. 22° E. 67.93'
S. 40° E. 39.05'
S. 28° W. 36.06'
N. 50° W. 41.10'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

3-14-97