

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZO
RECEIVED FOR RECORD

'95 DEC 8 AM 10 5

For corners in
Kalamazoo
(County)

Located In:

Corner Code #

Cooper Twp.

1. Public Land Survey

T 1S R 11W

K5

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Section

S T R

James D. Hahn

CLERK-REGISTER

LIBER

1 1390

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5										●			
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary D. Hahn, in a field survey on April 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 Corner Post established by U.S. Deputy Surveyor John Mullett.
Accessories: W. Oak 8in S42°W 15 1k. W. Oak 18in N53°E 13 1k.

1877 E. Strong Co. Sur. "Stake set from 1 US stump."

Date? K.C.R.C. notes: (Stake over stone)
Accessories: (H) B.W. 18 N3E 91 1k.
(H) Apple 12 N45 E 88 1k.
(H) B.O. 16 S30E 61½ 1k.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories not recovered.

Found ½" rebar in monument box 4' North of road centerline.
Found 2" dia. well point (point up) 15" below surface. (4.8' long)
Found 8"x10"x30" stone at 4' depth in sand with small stones around. Stone was on its side. Straightened and was good +/-.
Found large stone at 6.8' depth with prominent high point directly under 1/2" rebar in mon. box.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-15-95

R 28

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K5, Southeast corner Section 11, T1S, R11W, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. Position of 1/2" rebar and large stone is accepted as a careful and faithful perpetuation of the position of the original corner. Laid 8"x10"x30" stone on its side over large stone and set a 30" Harrison monument in monument box.

Fnd. P.K. nail in wood fence post N66°W 72.25'

Fnd. P.K. nail in 7" Pine S6°W 35.88'

Fnd. P.K. nail in 5" Oak S42°E 39.55'

Center of metal gate post S34°W 41.75'



Signed by *Gary D. Hahn*

Date December 5, 1995

Surveyor's Michigan License No. 38116