

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 323

CLERK - REGISTER

Handwritten signature

98 OCT 12 PM 1 29

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

For corners in Cooper Township
Kalamazoo
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>11W.</u>	<u>K-11</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

6. IWM Job No. 29584

I, Allen H. McMachen, in a field survey on May, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1827 - John Mullet, D.S.
 Set post corner to Secs. 25, 26, 35 & 36
 Wh. Oak 14" S. 12° E. 27 lks
 Wh. Oak 14" N. 04° W., 13 lks.

1906 - Ed Strong, C.S.
 "Found 6" tile per Albertson"
 Bl. Walnut 3" S. 75° W. 0.51 ch. (33.66')
 Bl. Walnut 3" S. 55° W. 0.71 ch. (46.86')
 Iron West 0.49 ch.

1947 - William Wilkins, R.L.S.
 Records plat of "Little Ranches"
 L. 16, Pg. 35, shows meas. North
 from W¼ cor. @ 1325.09 feet to 1/8 cor.

1989 - John Corbit, R.L.S.
 Records plat of "Highland Bluff"
 L. 35, Pg. 9 & shows meas. from NW
 cor. to N¼ cor. @ 2656.00 feet

SURVEY & REMONUMENTATION

NOV 25 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SECTION

Found iron pipe in monument box. Measured S. 55° W. 47.18 feet to a found nail on North side of a 12" Walnut believed to be a 1906 witness tree. Removed pipe and box and dug to depth of 2.5 feet finding a 6" diameter tile pipe standing vertical with a pointed stone inside. Point on stone was directly below found pipe at surface. Measured East 2656.23 feet to N¼ cor. and meas. South 2650.12 feet to W¼ cor.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
6/11/98 *R.H.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found tile pipe is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Harrison Monument over pointed stone inside tile pipe and placed mon. box over, Accessories:

Double headed nail in NE side 10" Walnut N. 40° W. 52.10'
 Nail & Tab in South side 40" Oak N. 70° E. 37.35'
 NW corner 1' X 1' X 8' high conc. pillar S. 40° E. 30.50'
 Nail & Tab in North side 12" Walnut S. 55° W. 47.14'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 9/24/98