

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 325

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 98 OCT 12 PM 1 29
 CLERK - REGISTER

Register of Deeds Stamp & File Number

For corners in COOPER TWP
KALAMAZOO
 (County)

Located in: Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>11W.</u>	<u>K-12</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		R		
	S		R		
3. Miscellaneous Property in Section	S		R		
	S		R		

SURVEY & REMONUMENTATION

NOV 25 1998

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____ **SECTION** _____
 6. IWM Job No. 29584

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5						3		2			1
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Allen H. McMachen, in a field survey on May, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - John Mullet, D.S., Set quarter Section post, Wh. Oak 14" S. 15° E. 8 lks, Wh. Oak 16" N. 43° W., 40 lks.
- 1947 - William Wilkins, R.L.S., Records plat of "Little Ranches", L. 16, Pg. 35 shows measure from W $\frac{1}{4}$ corner North 1325.09' to 1/8 corner. Note on plat: "Point 'A' (W $\frac{1}{4}$ cor.) comes in conc. post. Monument placed 2' North of true corner".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete fence post constructed of 4 individual wedge shaped posts bound with barb wire. Found concrete plat monument 2' North of centerline concrete post. Post is 5' tall. Measured North 2650.18' to Harrison Monument at NW corner.

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 6/11/98 R. J. G.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found concrete fence post is accepted as the best available evidence of the position of the original corner. The Kalamazoo County Remonumentation Peer Group decided to accept the found concrete fence post as the physical monument occupying the position of the corner, Accessories:

- Concrete plat monument North 2.00'
- Double headed nail in West side 24" Oak N. 04° E. 5.79'
- Double headed nail in West side 8" Cherry N. 06° W. 27.88'
- Double headed nail in North side 16" Oak S. 88° W. 28.85'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 10/9/98