

FEB 08 1998

PAGE 409

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Kalamazoo (County), Cooper Township, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., Located In: T 1S R 11W, Corner Code# M-7

4. Lot No. , Recorded Plat
5. Private Claims

I, Gary D. Hahn, in a field survey on April 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Established by U.S. Deputy Surveyor John Mullett - W. Oak 12" S 62 W 22 lks. W. Oak 8" N 42 W 15 lks.

1863 - V. 6 P. 417 - "stakes and stones"

1870 - F. Hodgman - "Found stake and stone correct by stump of 1 witness. Put in iron sleigh shoe stake and marked." W. Oak 18" S 87 3/4 E 164 lks. Wh. Oak 12" S 40 W 108 lks.

1932 - KCRC Road Const. Plans - NE Cor. Sec. 24 iron - W.O. 15" N 45 W 44.9' R.O. 10" N 80 E 39.2' R.O. 30" N 20 W 83.3'

1990 - Wilkins & Wheaton - " 2" pipe"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. Found 1/2" rod in 2 1/4" dia. 3" long pipe in asphalt road. Found 4"x6"x8" stone w/point leaning swly. at 5.8' depth. Found crockery below and around stone. Found 3/8" x 2 1/4" sleigh shoe standing vertically directly below stone. Sleigh shoe is 0.71' S and 2.07' W of 1/2" rod. Sleigh shoe is at depth of 6.6' below asphalt. Put crockery and stone back over sleigh shoe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7, Northeast Corner Section 24, Town 1 South, Range 11 West, ratified by Kalamazoo County Remonumentation Peer Group on May 21, 1998. Position of the sleigh shoe is accepted as a careful and faithful perpetuation of the position of the original corner. Set 30" Harrison Monument in a Monument Box directly over sleigh shoe.

Witness Ties:

- Fnd. P.K. Nail in 32" Oak N 80 E 38.64'
Fnd. P.K. Nail in 12" Oak S 85 E 42.62'
Set P.K. Nail in 10" Hickory N 60 W 93.02'
Set 1/2" rebar at edge of asphalt south 60.88'
Harrison Monument in Mon. Box (NW. Cor. Sec. 19, T. 1 S., R. 10 W.) North 42.17'

Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 12/21/98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN.28,1971
REVISED MAY 14,1975
REVISED JAN., 1983 REVISED OCT., 1995

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 3 05
J. H. [Signature]
CLERK - REGISTER

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

5/21/98 [Signature]

