

SURVEY & REMONUMENTATION

FEB 26 1998

LIBER 2 PAGE 226

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'97 NOV 7 PM 3 38

SECTION
Cooper Twp.
For corners in Kalamazoo
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: _____ Corner Code # _____

Smith Johnson

CLERK - REGISTER

1. Public Land Survey	T	<u>1S.</u>	R	<u>11W.</u>	<u>M-10</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

6. IWM Job No. 26019

I, Allen H. McMachen, in a field survey on June 14, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - John Mullett, D.S.
Set quarter Section post
Wh. Oak 12" S. 20° W. 16 lks.
Wh. Oak 10" S. 43° W. 25 lks.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
9/10/97 *R.E.S.*

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found axle shaft with broken crockery around. Dug around shaft and found oblong stone lying on East side. Continued digging to bottom of shaft (4.8' below grade) and found a few baseball size stones at bottom. Being the only stones encountered during excavation. Found 1/2" iron rod (West quarter corner, Section 30, Richland Township) 28.15 feet North of shaft. The mean of G.L.O. notes jogs is 28.05 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found axle shaft is accepted as the best available evidence of the position of the corner. Replaced axle shaft with a 30" Harrison Monument, Accessories:

Nail & Tab in East side 12" Cherry N. 30° E. 41.82'
Nail & Tab in Northeast side 10" Oak S. 50° E. 32.77'
Nail & Tab in North side 24" Oak N. 40° W. 15.46'
Metal fence post N. 45° E. 26.73'



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 10/28/97