



LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COOPER TWP  
KALAMAZOO  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 1S. R 11W. M-12  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

SURVEY &  
REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

6. IWM Job No. 31048

I, Allen H. McMachen, in a field survey on May 27, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 - John Mullett, D.S., Set quarter Sec. post, Wh. Oak 16" S. 60 1/2° W. 21 lks., D. O. 18" N. 39° W. 46 lks..
- 1961 - Robert Gove, R.L.S., Records plat of "Rolling Ridge Acres" L. 27, Pg. 14 placing a monument 33.0' West of E 1/4 cor., Sec. 36, Cooper Twp..

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
6-17-1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "PK" nail 8.24' South of a standard marker at the W 1/4 cor., Sec. 31, Richland Twp. (the mean of G.L.O. jogs is 8.25'). Dug below "PK" nail and found 60d nail 0.5' below surface in road gravel (pavement 4" thick). Continued digging and found 3 bricks forming a rough triangle. The center of said triangle was directly below both found nails. Found bricks were 2.7' below grade. Removed bricks and dug to depth of 4' finding no additional evidence of corner. Also excavated at the split of the Cooper mile to depth of 4' and found no evidence of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The position of the found nails above ring of brick is accepted as the best available evidence of the position of the original corner. Placed a 30" Harrison Monument at position of found nails with monument box over, Accessories:

- Concrete plat monument West 33.02'
- "PK" Nail in South side of 24" Maple N. 70° E. 72.13'
- "PK" Nail in S.E. side of Twin 12" Elm S.32° W. 55.77'
- "PK" Nail in West side of U. Pole S. 18° E. 65.03'



Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 11/6/99