

SURVEY & REMONUMENTATION

AUG 06 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Kalamazoo

(County)

Alamo Twp.

Located In:

Corner Code #

- | | | | |
|--------------------------------------|---------------|----------------|-------------|
| 1. Public Land Survey | T <u>1</u> S. | R <u>12</u> W. | <u>A-03</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

CLERK - REGISTER

[Signature]

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'96 JUN 7 PM 2 26

LIBER 2 PAGE 020
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on March 19, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: United States Government Surveyor's; intersected West boundary 112 lks. North of post. Set post at intersection common to Sections 6 and 7.
Beech 16" S. 82° E. 21 lks.
Elm 26" N. 21° E. 14 lks.
- 1875: E. Strong, County Surveyor; found jog 1.19 lks. from the 4 U.S. stumps of bearing trees. Stone and stake and 1 brick at each post.
- 1886: E. Strong, County Surveyor; set brick and stake using Pine Grove corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1975: Dennis Middleton, R.L.S. #16049; L.C.R.C. L-1, P-583 found stake and brick 24" below surface of road. Set iron bar over brick to surface of road.
- 1996: Found 1/2" x 24" long iron bar over stake, found a few chips of brick below iron.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-18-1996 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-03: Northwest corner of Section 7, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stake as set by E. Strong, County Surveyor, in a 1886 survey. Placed 16" of Harrison Monument over stake in monument box in concrete.

- | | | |
|--|-----------|--------|
| PK Nail on East Side of 24" Wild Cherry | N. 38° E. | 38.91' |
| PK Nail on North Side of 28" Maple | N. 84° E. | 46.45' |
| PK Nail on East Side of 8" Elm | S. 46° W. | 41.91' |
| Nail and Tab on North Side of Telephone Pole | N. 50° W. | 29.64' |

Signed by *Robert E. Snell*

Date 6-6-96

Surveyor's Michigan License No. 9734

