

SURVEY & REMONUMENTATION

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALAMO TWP
KALAMAZOO Located In:
(County)

Corner Code #

1. Public Land Survey	T	1S	R	12W.	A-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 30 PM 12 00
LIBER 2 PAGE 441

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen, in a field survey on December, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:
Corner not placed by original government surveyors.
No Historic information found.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-17-1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron pipe 64.61 feet (mean of government jogs = 64.68 feet) North of a standard Van Buren County Remonumentation Monument at the East quarter corner, Section 12, Pine Grove Township. Measured from found pipe North 2635.46 feet to a standard marker at the Northwest corner, Section 7, Alamo Township and measured South from found pipe 2641.21 feet to a standard marker at the Southwest corner, Section 7, Alamo Township. Determined that found pipe ~~at said West quarter corner~~ was 2.88 feet South of true corner location at bisection of West Section line. Placed a 21" Harrison Monument at bisection of West Section line and on line between said Northwest corner and Southwest corner of Section 7. Excavation below found pipe and at position of bisection did not disclose additional evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original government surveyors. 21" Harrison Monument placed is accepted as the best available evidence of the position of the corner, Accessories:

- Nail & Tab in North side of 16" Maple S. 64° E. 27.2'
- Nail & Tab in East side of 24" Maple S. 23° W. 6.47'
- Nail & Tab in East side of 16" Ash N. 02° E. 19.97'
- Nail & Tab in East side of 6" Elm N. 52° E. 20.35'
- ±30.5' South of fence to East
- 4' East of North-South fence

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/29/98

