

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAMO TWP
KALAMAZOO

(County)	Located In:	Corner Code #
1. Public Land Survey	T 15R 12W. A-5	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 30 PM 12 00
LIBER 2 PAGE 442
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Allen H. McMachen, in a field survey on December, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 12-17-1998

A. Description of original monument and accessories and/or subsequent restoration:
1827 - William Brookfield, D.S. (N.E. cor., Sec. 13, Pine Grove Twp.), Ran North on East boundary of Section 13 a distance of 80 chains (5280') and set post corner. 7" Beech S. 67° 45' W. 31 lks. (20.46'), 7" Elm N. 39° 30' W. 9 lks. (5.94'), Distance West is 79.02 chains (5215.32').
1830 - Robert Clark, Jr., D.S., Intersected West boundary 84 lks. North of post. Set post at intersection. Corner to Sections 7 and 18. Bl. Ash 15" S. 78° E. 33 lks., Maple 16" N. 49° E. 48 lks..
1875 - Ed Strong, Deputy Surveyor, Maple 8" S. 84° E. 27 lks. (U.S. gone), B. Ash 6" S. 31½° W. 6½ lks. (U.S. gone), B. Ash 12" N. 28° E. 35 lks..

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1½" O.D. pipe. Verified position of corner by measuring from a standard marker at the East quarter corner, Section 12, Pine Grove Township, South 5250.04 feet to a standard marker at the East quarter corner, Section 13, Pine Grove Township. Bisected mile measure (5250.04' ÷ 2 = 2625.02') and established temporary location of Southeast corner, Section 12 at 2652.02 feet South of said East quarter corner, Section 12. Measured Northerly 54.18 feet to said found 1½" O.D. pipe. Said found pipe was 54.18' North and 2.11' West of said bisection point (said found pipe in line with fence to East and in remnants of fence to North and South). Held North-South position of found pipe for the North line of Section 18, Alamo Township and held East-West position of corner on line between said East quarter corner, Section 12, Pine Grove Township and said East quarter corner, Section 13 Pine Grove Township which is 2.11 feet East of found pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Position of corner per above description is accepted as a careful and faithful reestablishment of the position of the original corner, placed a 20" Harrison Monument as said position,
Accessories:

- In line with fence to East
- Nail & Tab in 12" Ash S. 15° W. 28.78'
- Nail & Tab in 6" Ash S. 70° E. 18.35'
- Nail & Tab in 5" Maple N. 05° W. 28.28'
- Nail & Tab in 8" Ash S. 75° W. 23.36'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/29/98

