

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAMO TWP
KALAMAZOO

Located In: _____ Corner Code # _____

1. Public Land Survey

T 1S. R 12W. A-6

2. Property Controlling in Section

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on December, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.
1902 - Ed Strong, C.S., "E¹/₄ post of Pine Grove Twp. found stake. Both U.S. stumps plain. Iron pipe. Elm 7" N.
85° W. 10 lks., Maple 8" S. 70° E. 23 lks..



RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

12/17/98
A.H. McMachen

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner marker found. Established position of corner at the bisection of the West line of Section 18. Placed 21" Harrison Monument 2633.33 feet South of a standard marker at the Northwest corner, Section 18. Monument placed also being 2633.33 feet North of reestablished position of the Southwest corner, Section 18 (Southwest corner, Section 18 being reestablished at 38.28 feet (government jog) North of a standard Van Buren County Remonumentation Monument at the Southeast corner, Section 13, Pine Grove Township). Said West quarter corner, Section 18, Alamo Township is on line between said Northwest corner, Section 18 and said Southwest corner, Section 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
This position not established by original government surveyors. 21" Harrison Monument placed is accepted as the best available evidence of the position of the corner, Accessories:

- ±2.5' East of fence remnants North & South
- Nail & Tab in N.W. side of 6" Maple N. 59° E. 11.18'
- Nail & Tab in S.W. side of 6" Ash S. 61° E. 24.45'
- Nail & Tab in West side of 8" Ash S. 10° W. 23.92'
- Nail & Tab in North side of 8" Ash S. 80° W. 6.1'
- East quarter corner, Section 13, Pine Grove Township (standard Van Buren County Remonumentation Monument) South 45.87'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 2/4/99