

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 445

For corners in ALAMO TWP
KALAMAZOO
(County)

Located In: Corner Code #

1. Public Land Survey	T	1S.	R	12W.	A-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 30 PM 12 00
LIBER - REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on December, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.

1830 - Robert Clark, Jr., D.S., (Placing N.W. corner, Sec. 19), Intersected West boundary 58 lks. North of post. Set post at intersection. Corner to Sections 18 & 19. Bl. Ash 13" S. 60° E. 20 lks., Bl. Ash 13" N. 73° E. 30 lks..

1830 - Robert Clark, Jr., D.S., (Placing S.W. corner, Sec. 19), Intersected West boundary 35 lks. North of post. Set post at intersection. Corner to Sections 19 & 30. Elm 10" S. 45° E. 13 lks., Wh. Ash 14" N. 56° E. 18 lks..

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 12-17-1998

No corner marker found. Position of corner established by measuring between the two closest Van Buren County Section corners North and South, said corners being a 1 1/2" pipe found at the East quarter corner, Section 13 (per 1901 W.H. Goss, D.C.S.) and a 1 1/2" pipe found at the East quarter corner, Section 25 (per 1915 W.H. Goss, D.C.S.). The distance measured between said corners is 10,502.97 feet. Divided this measure into 4 equal half miles (10,502.97 ÷ 4 = 2625.74') and established position of Northeast corner, Section 24 Pine Grove Township at 7877.23 feet North of said East quarter corner, Section 25 and placed Northwest corner, Section 19, Alamo Township North at the government jog of 38.28'. Also established position of the Southeast corner, Section 24, Pine Grove Township 2625.74 feet North of said East quarter corner, Section 25, and placed Southwest corner, Section 19, Alamo Township North at government jog of 23.10 feet. Measured between said Northwest corner, Section 19 and said Southwest corner, Section 19 at 5266.66 feet. Bisected the Kalamazoo County mile measure of 5266.66 feet and established position of West quarter corner, Section 19 at 2633.33 feet South of position of said Northwest corner, Section 19, Alamo Township. All corner locations between said East quarter corner, Section 13, Pine Grove Township and the East quarter corner, Section 25, Pine Grove Township are on a straight line. Position of West quarter corner, Section 19, Alamo Township is in ditch and is not readily accessible, therefore a monument was not placed at position of quarter corner, instead 4 standard markers were placed as witnesses on the West side of quarter corner, see sketch on reverse. Witness monuments have coordinate values as shown in Section "C" below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original government surveyors. This position (coordinate value = N. 5030.69, E. 5000.00) is accepted as a careful and faithful reestablishment of the position of the corner, Accessories:

- Position of East quarter corner, Section 24, Pine Grove Township (no corner in place-in ditch) South 30.69'
- Witness Mon. "A": 30" Slimline Standard Van Buren County Remonumentation Monument (coordinate value = N. 5000.00, E. 4965.00) West 35.00'
- Witness Mon. "B": 30" Slimline Standard Van Buren County Remonumentation Monument (coordinate value = N. 4950.00, E. 4965.00) S. 34° 59' 31" W. 61.03'
- Witness Mon. "C": 30" Harrison Monument (Kalamazoo County Monument) (coordinate value = N. 5030.69, E. 4965.00) N. 48° 45' 13" W. 46.55'
- Witness Mon "D": 30" Slimline Standard Van Buren County Remonumentation Monument (coordinate value = N. 5080.69, E. 4965.00) N. 23° 26' 57" W. 87.95'

Witnesses to witness monuments on reverse



Signed by Allen H. McMachen Date 12/24/98

Surveyor's Michigan License No. 16935

Witnesses to Witness Monument "A"

- "PK" Nail & Tab in North side 14" Maple N. 68° E. 5.27'
- "PK" Nail & Tab in S.W. side 14" Maple S. 22° E. 22.58'
- "PK" Nail & Tab in 14" Maple S. 80° W. 25.67'
- "PK" Nail & Tab in North side 12" Maple N. 56° W. 20.98'

LIBER

2PAGE 446

Witnesses to Witness Monument "B"

- "PK" Nail & Tab in S.W. side 6" Elm S. 25° W. 32.09'
- "PK" Nail & Tab in West side 18" Maple S. 22° E. 27.85'
- "PK" Nail & Tab in South side 14" Ash N. 74° E. 16.46'
- "PK" Nail & Tab in West side 16" Maple N. 51° W. 4.70'

Witnesses to Witness Monument "C"

- Nail & Tab in 12" Maple East 9.82'
- Nail & Tab in 12" Maple S. 25° W. 29.35'
- Nail & Tab in 14" Maple S. 05° E. 27.63'
- Nail & Tab in 6" Ash N. 60° W. 16.27'

SURVEY &
REMONUMENTATION

FEB 08 1999

SECTION

Witnesses to Witness Monument "D"

- Nail & Tab in 18" Maple East 12.32'
- Nail & Tab in 18" Maple N. 50° W. 14.27'
- Nail & Tab in 14" Double Maple N. 10° E. 31.59'

