

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 443

ALAMO TWP

KALAMAZOO

(County)

Located In:

Corner Code #

1. Public Land Survey

T 1S. R 12W.

A-9

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Section

S T R

4. Lot No. , Recorded Plat

5. Private Claims

OLDFR - REGISTER

*Allen H. McMachen*

98 DEC 30 PM 12 00

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Allen H. McMachen, in a field survey on December, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - Robert Clark, Jr., D.S., Intersected West boundary 35 lks. North of post. Set post at intersection. Corner to Sections 19 & 30. Elm 10" S. 45° E. 13 lks., Wh. Ash 14" N. 56° E. 18 lks..

1875 - Ed Strong, Deputy Surveyor, "Found stake 2 U.S. one good"

1902 - Ed Strong, C.S., From square post recently set by Goss from Elm Northwest of U.S. allowed 35 lks. North for jog to corner of Section 30 (Strong's map shows measure from Northwest corner, Section 30 to West quarter corner Section 30 at 39.86 1/2 chains [2631.09]).

1902 - Ed Strong, C.S. (West quarter corner, Section 30), "Bisected West Section line of 30, set stake, iron & brick promised. Jog on County line at 1/4 post is 28 lks. by this survey. Goss, County Surveyor for Van Buren had just brushed & staked this Section line for Todd & we followed the line."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner marker found. Position of corner established by measuring between the two closest Van Buren County Section corners North and South, said corners being a 1 1/2" pipe found at the East quarter corner, Section 13 (per 1901 W.H. Goss, D.C.S.) and a 1 1/2" pipe found at the East quarter corner, Section 25 (per 1915 W.H. Goss, D.C.S.). The distance measured between said corners is 10,502.97 feet. Divided this measure into 4 equal half miles (10,502.97 ÷ 4 = 2625.74') and established position of Southeast corner, Section 24, Pine Grove Township at 2625.74 feet North of said East quarter corner, Section 25 and placed a 30" Harrison Monument at Southwest corner, Section 19, Alamo Township North at the government jog of 23.10'. Said Southwest corner, Section 19 is on line between said East quarter corner, Section 13, Pine Grove Township and the East quarter corner, Section 25, Pine Grove Township. Measured South to West quarter corner, Section 30, Alamo Township (said West quarter corner being 28 lks. North of East quarter corner, Section 25, Pine Grove Township per 1902 information) at 2630.36'.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12-17-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Monument as placed per above description is accepted as a careful and faithful reestablishment of the position of the original corner, Accessories:

- Nail & Tab in Quad Ash N. 20° W. 16.32'
- Nail & Tab in Quad Ash N. 45° W. 11.83'
- Nail & Tab in 4" Maple East 30.23'
- Southeast corner, Section 24, Pine Grove Township (Slimline Standard Van Buren County Remonumentation Monument) South 23.10'
- ±2' West of West edge ditch



Signed by *Allen H. McMachen*

Date 12/29/98

Surveyor's Michigan License No. 16935