

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 399

For corners in Alamo Twp.

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>1</u> S R <u>12</u> W	C-01
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

CLERK - REGISTER

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 9 15

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Sept. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors; intersected base line. Set post at intersection corner to Sections 5 & 6.

Beech 18" S. 17° E. 41 lks.
Beech 10" S. 09½° W. 42 lks.

1875: E. Strong, County Surveyor; Vol. 6 P. 505 NE Corner S(take) Elm 14" N. 43½° W. 15 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Found 1" iron pipe measured 85.0 ft. (1.30 lks.) East for Northeast corner after running from Northwest corner Section 6, T. 1 S., R. 12 W.

Northwest to North 1/4 post = 1,639.834
North 1/4 post to Northeast corner = 2,629.62

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11/19/98 R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-01: Northeast corner, Section 6, T. 1 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on November 19, 1998 as a careful and faithful re-establishment of the position of the original corner. Placed 30: Harrison monument after re-establishment of corner. See "B" above.

PK Nail in South Side	12" Maple	N. 75° W.	66.58'
PK Nail in East Side	16" Oak	South	14.75'
PK Nail in South Side	12" Hickory	East	32.76'
PK Nail in Southeast Side	14" Oak	N. 25° E.	15.65'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-18-98