

FEB 26 1998

LIBER 2 PAGE 228

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'97 NOV 7 PM 3 38

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Township
Kalamazoo
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1S. R 12W. C-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Smith
CLERK - REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 30177

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 5, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - Robert Clark, D.S., "Set 1/4 Section corner, Bl. Oak 30" N. 73° W. 52lks., Elm 15" N. 25° E. 85 lks..

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod 4 feet North of fence line to East and 20 feet South of occupation line (row of pines) to West. Dug for corner and found no additional marker. Origin of found iron was not determined. Placed iron rod on line and midway between a Harrison Monument at the Southeast corner and a found "T" iron at the Northeast corner of Section 19. Measured North 2640.90 feet to said "T" iron and measured South 2640.90 feet to said Harrison Monument.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8/21/97 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Iron rod placed is accepted as the best available evidence of the position of the corner. Replaced iron rod with a 30" Harrison Monument and Monument Box, Accessories:

- Existing Nail & Tab in West side U. Pole N. 30° E. 84.59'
- Nail & Tab in South side 24" Maple S. 80° E. 31.68'
- Nail & Tab in Southeast side 10" Pine S. 40° W. 56.81'
- Nail & Tab in Southwest side 18" Chestnut N. 30° W. 59.73'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 11/4/97