

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alamo Township
Kalamazoo (County)

Located In: Corner Code #

- 1. Public Land Survey T 1S. R 12W. C-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 SEP 26 AM 11 10
Clerk - Register

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on June 5, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column C and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - Robert Clark, D.S., Set post cor. to Sec. 19, 20, 29 & 30, Lynn 13" N. 60° W. 5 lks., Bl. Oak 16" N. 05° E. 33lks.

1875 - Ed Strong, C.S., "Apple 5" S. 40 1/2° E. 76 lks. stone", Shows on map measure from S.E. cor., Section 30 to E 1/4 cor., Sec. 30 at 2658.15' and "variation" on said line of 6°. Also shows measure of 2631.42' between said E 1/4 cor. and the NE cor. of Section 30 and a variation of 6° 06'.

1972 - Consumers Power Company, Shows SE corner, Sec 19 as a found corner and shows measure of 2638.37' from said SE corner, Sec. 19 to the E 1/4 cor., Sec. 19.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod per 1972 information 11' North of fence to East and 15' North of fence to West. Found iron is also approximately 1/3 of the distance between a found iron at E 1/4 cor., Sec. 30 and a found "T" iron at the NE corner, Sec. 19 and very nearly on line between said corners. No evidence was found on how iron was placed or by who. Due to iron being so far North of existing fence lines and no history this iron was not used for section corner. Established Section corner by measuring between found pointed stones at SE corner and the E 1/4 cor., Section 30 at 2660.94', Ed Strong (1875) measured 2658.15' and a variation of 6°. Strong (1875) also measured 2631.42' between E 1/4 corner and NE corners of said Sec. 30 and a "variation" of 6° 06'. Compared current and 1875 measures between SE cor. & E 1/4 cor., Sec. 30 and held that proration against Strongs 1875 measure of 2631.42' between E 1/4 cor., and NE cor. Producing a distance of 2634.18'. Established East-West position of corner by turning angle of 180° 06' at E 1/4 cor., Sec 30 in the Western quadrant matching Strong's "variations". Dug extensively in this area and found 4 baseball size stones directly below position described above. Stones found were the only stones located in all excavation and the same size as those found around the large pointed stone recovered at the SE cor., Sec. 30.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The above described corner location was accepted as the best available evidence of the position of the corner. Placed Harrison Monument at said above location with Mon. Box over, Accessories:

- Nail & Tab in Northwesterly side U. Pole N. 40° E. 60.45'
Nail & Tab in Northwesterly side 10" Pine S. 20° E. 73.67'
Nail & Tab in Northeasterly side 40" Sassafras N. 45° W. 55.60'
N.E. cor. house #6985 S. 65° W. 82.50'
3.5' East of centerline N.-S. road

RATIFIED BY KALAMAZOO COUNTY PEER GROUP 8-21-1997



Signed by Allen H. McMachen

Date 9/25/97

Surveyor's Michigan License No. 16935